UPG 450 IN LINE

MINI CRANES

- 300 kg bearing (4 pieces)
- 450 kg bearing (6 pieces)
- Vacuum suction plate system
- Acoustic alarm
- Modular design
- · Approx. 8 hours drive time

Specifications

Technical Data Vacuum system Suction plate

Two-circuit system 4 pieces x 300 mm 6 pieces x 300mm

Load capacity

300 kg (4 pieces) 450 kg (6 pieces)

Weight

47 kg (4 pieces) 57 kg (6 pieces)

Operating drive time

12 V battery, 7 Ah - 8 hours


High flexibility due to modular design

Removable load arm and extensions for additional suction plates

Suspension eyelets, for vertical mounting without load arm

Ergonomic hand slide valve





Thanks to its modular design, the 450Kg SWL can be easily and quickly adapted. The standard 4 suction cups can be extended to 6 pieces without tools. The detachable load arm provides additional flexibility.

The 450Kg SWL has hanging eyelets for vertical mounting without load arm and an ergonomic hand slide valve. The attached suction plates ensure good adhesion and application power on the construction site. The 450Kg SWL automatically performs the suction process by buttonpress. 450Kg SWL also monitors vacuum pressure automatically.



